

LEWEY LAKE CAMPGROUND SEQUENCED DOSING CHAMBER

As-built

All outlet inverts 4" off floor.

CueBox model: QB3-30. Trigger manifolds set at 30" above floor for 22" drawdown WITH 4" BUILT-ON SHIMS

Flout models:

2- FL2231-QR-4R 3" single Flout w/ right hand CueBox tap.
4" shim 22" drawdown

1-FL2231-QL-4R 3" single Flout w/ left hand CueBox tap.
4" shim 22" drawdown

Maximum liquid depth 30-31"

Minimum liquid depth 8-9"

Drawdown 22"

Rissy Plastics, LLC
350 Cedar Lane
Torrington, CT 06790
860-482-1645
877-221-4426
www.flout.net

FLOUT® US Pat. 5290434
CueBox™ US Pat Pend
©2010 Rissy Plastics, llc

